

Toondoon Project Mineral Resource - 2025

Resource Category	Lithology	Volume (Mm ³)	Density (T/m ³)	Tonnes (T)	Al ₂ O ₃ %	Fe ₂ O ₃ %	SiO ₂ %	TiO ₂ %	LOI %	K ₂ O %	Cut-Off Grade
Measured	Bauxitic Clay	750,000	1.66	1,250,000	38.81	13.86	21.92	4.53	20.07	0.06	No cut-off applied
Measured	Plastic 'Grey' Clay	1,380,000	1.46	2,010,000	35.45	4.98	41.39	3.38	14.20	0.02	No cut-off applied
Measured	Kaolinite 'Pink' Clay (High Iron)	510,000	1.42	720,000	36.79	1.92	44.92	2.19	13.63	0.05	No cut-off applied
Measured	Kaolinite 'White' Clay (Low Iron)	900,000	1.44	1,300,000	37.48	0.41	46.50	1.59	13.43	0.12	No cut-off applied
Measured	Sandy Clay	800,000	1.65	1,320,000	26.79	0.73	61.24	1.21	9.52	0.05	23% Al ₂ O ₃
Indicated	Bauxitic Clay	1,510,000	1.66	2,510,000	37.04	16.05	22.62	4.19	19.43	0.05	No cut-off applied
Indicated	Plastic 'Grey' Clay	2,620,000	1.46	3,830,000	35.22	4.84	42.09	3.15	14.06	0.03	No cut-off applied
Indicated	Kaolinite 'Pink' Clay (High Iron)	950,000	1.42	1,350,000	36.48	2.32	45.24	1.85	13.49	0.08	No cut-off applied
Indicated	Kaolinite 'White' Clay (Low Iron)	1,150,000	1.44	1,660,000	37.57	0.40	46.43	1.58	13.41	0.12	No cut-off applied
Indicated	Sandy Clay	1,460,000	1.65	2,410,000	26.10	0.76	62.15	1.21	9.25	0.05	23% Al ₂ O ₃
Inferred	Bauxitic Clay	480,000	1.66	800,000	30.73	27.86	22.44	3.19	15.18	0.03	No cut-off applied
Inferred	Plastic 'Grey' Clay	510,000	1.46	740,000	34.19	5.88	42.41	3.55	13.31	0.03	No cut-off applied
Inferred	Kaolinite 'Pink' Clay (High Iron)	110,000	1.42	160,000	34.81	6.00	44.02	1.46	13.07	0.15	No cut-off applied
Inferred	Sandy Clay	190,000	1.65	310,000	28.04	2.22	57.93	1.19	10.12	0.06	23% Al ₂ O ₃